KOLAR DIVISION.

Notice.

The attention of the public is drawn to the notification published in the *Mysore Gazette*, dated the 14th February 1918, Part IV, pages 148—149, calling for tenders for constructing a separate building for the Anglo-Vernacular School at Bowringpet.

Dated 7th February 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 8th March 1918, for restoring the Keelkoppa Uppakere minor tank, R. No. 696 of Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Keelkoppa Uppakere minor tank, R. No. 696, Bowringpet Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring the Keelkoppa Uppakere minor tank, Registered No. 696 of Bowringpet Taluk.

Items	Unit	Quantity
Bund R. L. 54·50—		
Earthwork including watering and tamping	C. yd.	8,649
Do for breach do	"	4,722
Removing sand and silt from the breach	"	975
Turfing	S. yd.	3,548
New stone work (revetment)	C. yd.	1,831
Old stone work (revetment)	"	256
Providing grade with index stones including painting and cutting figures	No.	21
B. M. stones do	"	2
Registered No. and date stones do	"	2
Waste weir left 175 feet long—		
Earthwork excavation chargeable to bund	C. yd.	250
Burnt brick in surki mortar	C. ft.	15·75
Plastering with surki mortar	Sqr.	17·37
Burnt stone slabs 6" thick	S. ft.	403
Rough stone work, new 6	C. yd.	201
Waste weir right 50 ft. long R. L. 50·00—		
Earthwork excavation chargeable to bund	"	89
Burnt brick in surki mortar	C.ft.	273
Plastering with surki mortar	Sqr.	4·90
Burnt stone slabs 6" thick	S. ft.	210
Rough stone work, new	C. yd.	77

V. V. KARVE,
Offg. Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

Attention is invited to the notice calling for tenders for improving and extending A.-V. School at Kunigal, published in Part IV of the *Mysore Gazette* dated 14th February 1918, page 149.

N. G. KRISHNA IYENGAR,
Offg. Executive Engineer.